

Do right.

Do your best.

**Treat others as
you want to be
treated.**

*Lou Holtz
Coach*

**Obstacles are
things a person
sees when
he takes his
eyes off his goal.**

*E. Joseph Cossman
Entrepreneur*

Kiowa County Commons: Greensburg, KS

Construction is well underway on the 20,210 sq. ft. multipurpose facility called the Kiowa County Commons. It is located at 301 S. Main in Greensburg, KS, south of the new City Hall. When the structure is completed, it will house the 5,200 sq. ft. HD television Media Center, the Greensburg branch of the Kiowa County Library, the Kiowa County Discovery Center and Museum plus the Kiowa County office of K-State Research and Extension. Just inside the main entry visitors will also find a restored turn of the century soda fountain salvaged from the tornado rubble of the local Hunter Drug Store. The building, built to LEED Platinum standards, will have many environmental sustainable elements: large amounts of glass on the north to allow light to enter, photovoltaic panels on the roof to provide electrical power from solar rays, a living roof, water conservation fixtures and the use of insulated concrete



form (ICF) walls. At this time the ICF walls are complete, the steel will be finished by Dec. 1st and the masonry is progressing well. Architect for this project is Matt Cortez of GLMV Architecture. The Estimator/Project Manager is Gib Compton. David Spoon is the Job Superintendent. The building is scheduled to be completed in May.



www.glmv.com/.../kiowa-county-commons/

Employee Spotlight: Sabastin Runnion, Carpenter/Welder

INSIDE THIS ISSUE:

Job Spotlight	1
Employee Spotlight	1
Completed Projects	2
Current Projects	3
Mission Statement	4
Current Projects (cont.)	4



Sabastin Runnion is a graduate of El Dorado High School. He has worked for Compton Construction Corporation since 2006 as a carpenter. He recently added welding certification to his list of skills. Sabastin has worked in construction a total of thirteen years. While in high school, his first job was as a laborer on residential framing jobs. His favorite aspect of carpentry is seeing the project come together and having both the client and himself pleased with the end result. His favorite job while at Compton Construction has been the Gordon Parks Academy completing the challenging task of customizing all the window sills to fit tight and properly. Sabastin is married with three young boys who keep he and wife very busy with a variety of activities. He enjoys volunteering for his son's Cub Scout group whenever needed. Deer hunting is a favorite hobby, that the boys leave little time for. He and wife enjoy catching a movie and dinner whenever possible.

Completed Projects

HVAC Renovation First United Methodist Church: El Dorado, KS



Structure completed in 1927.

Installation and remodel work was completed in August at the First United Methodist Church at 421 West Central Ave. in El Dorado, KS. The renovation of 12,000 sq. ft. involved removing the old boiler system and installing a forced air system. The project also included drywall and acoustical ceiling work. Vince Haines of PKHLS of El Dorado was the architect. Chris Jackson was Estimator/Project Manager teamed with Coy Gannon as Job Superintendent.



During renovation

Presbyterian Manor Addition & Remodel: Arkansas City, KS



New therapy room.

Construction was completed in mid November on a 1600 sq. ft. addition to the Presbyterian Manor located in Arkansas City, KS at 1711 N. 4th St. A new therapy room is located in this new addition. At the same time the assisted living area received a face-lift of floor coverings, ceilings, fixtures, and doors. Architect for this project was Fred Britain of PKHLS of Eldorado, KS. Adam Doll was the Estimator/Project Manager with Marty Kerr as Job Superintendent.



Old Mill Plaza Fire Restoration: Newton, KS



Southeast view Old Mill Plaza



Renovation of banquet space shown in progress and complete.



Reception area for Hospice

The historic Old Mill Plaza was originally built in 1879. It was extensively damaged by fire on Nov. 23, 2009 in the unoccupied north and east wing areas of the facility. The roof of this area needed to be completely replaced. Fire restoration began in May on the 7,000 sq. ft. facility. Completion of Phase 1 in August allowed Hospice of Kansas to move into a 3,000 sq. ft. tenant area. Phase 2 involved the replacement of windows on the 2nd & 4th Floors. A 2400 sq. ft. banquet area was completed in November. George Krievens of PKHLS of Newton, KS is the architect involved in historical preservation. Gib Compton is Estimator/Project Manager with Alan Carlyle as Job Superintendent.

El Dorado Middle School Stage Renovation: El Dorado, KS

The El Dorado Middle School stage received a facelift beginning mid July to be ready in time for Fall performances by the middle school students. The project involved putting tongue and groove floor covering over 2,000 sq. foot. New stage rigging, lighting and curtains were also installed. David Wagoner, Director of Operations for USD #490 worked with Chris Jackson who was Project Manager for this project. Coy Gannon was Job Superintendent.



Current Projects

Cowley Co. Courthouse Window Replacement: Winfield, KS

Replacement of 4,000 Sq. ft. of windows began in August at the Cowley County Courthouse located at 311 E. 9th Ave. in Winfield, KS. The project is 75% complete. Approximately 126 windows of various sizes will be installed at an average of five windows per day. This project has taken a lot of coordination between the glass fabricators and installers of Wickham Glass and the schedules of the courthouse employees. The project is schedule to be completed by the end December. Gordon and Associates of Winfield, KS is the architect. Chris Jackson is the Estimator/Project Manager. Jason Rotramel is the Job Superintendent.



Courthouse completed in 1963.

Cooper Elementary Addition - USD 260: Wichita, KS



Before: Exterior of existing library.

The construction project at Cooper Elementary School began November 1st. The school, part of the Derby School District is located at 4625 Juniper. The project includes new construction and interior remodel work. 15,000 sq. ft. of the new construction will become a new library and FEMA shelter/gym with pre-cast wall. The existing library area will be converted into seven



Formation of ICF Block walls.

classrooms. ICF blocks and Concrete Masonry Units (CMU) are being used next to the existing building. Two new restrooms and the remodel of two existing restrooms are also included in this project. When completed a glass canopy will be over the corridor separating the existing building and the FEMA shelter. Matt Hamm of Schaefer Johnson Cox Frey Architecture is the architect. Chris Jackson is the Estimator/Project Manager. Steve Rotramel is the Job Superintendent.

Hawker Beechcraft Remodel - Wichita State University NIAR: Wichita, KS



On October 18, 2010, the remodel project for the NIAR program of Wichita State University began at the Hawker Beechcraft campus located at 370 N. Webb Road. 8,800 sq. ft. has been gutted to provide space for twelve new private offices and four open office areas. The project is scheduled to be completed the end of December. David White of Howard Helmer Architecture designed the project. Adam Doll is the Estimator/Project Manager working with Coy Gannon who is the Job Superintendent.

Air Capital Terminal 3 East Data Center: Wichita, KS

Work began the beginning of December on a remodel of 1500 sq. ft. of space at the Wichita Mid-Continent Airport to remodel the data center at Terminal 3. The space will be completely gutted and existing walls taken down. The project includes rebuilding the walls and painting. An epoxy floor will be created to produce a static free environment and dissipate any static people may have upon entering the room. The new, self-contained Liebert heating and cooling units will be installed within the room along with a back-up generator for equipment. While construction is taking place specific precautions must be in place to protect existing equipment. Erin Kiser from GLMV Architecture designed the project. Gib Compton is Estimator/Project Manger with Chris Eddy as Job Superintendent.



<http://www.visitingdc.com/airports/wichita-airport-address.asp>

COMPTON CONSTRUCTION CORPORATION

GENERAL CONTRACTOR

**1802 N. Washington
P.O. Box 3097
Wichita, Kansas 67201-3097**

Phone: 316-262-8885

Fax: 316-262-0080

Email: geompton@comptonconstruction.com

Web: www.comptonconstruction.com

Compton Construction Corporation: Mission Statement

Compton Construction Corporation emerged in the construction industry in 1997. It continues to grow both in size and reputation. Since our beginning we have held onto three principles for success: hard work, fairness, and quality. We work to provide our clients with the service they need and the quality they expect. Our future looks bright as we continue to expand our operations. Regardless of size, Compton Construction Corporation's main priorities are to continue providing our clients with outstanding service and satisfaction.

Current Projects (cont.)

WSU Batters Eye: Wichita, KS

As Spring practice for Shocker Baseball quickly approaches, work has begun on building a 72 ft. by 32 ft. tall wind screen behind the center field wood fence. The steel structure which will be welded on sight will hold 16' x 8' green, nylon panels. The purpose is to create a clean backdrop for the batter to pick up the ball with their eye. The architect is Brandon Gibson of Spangenberg Phillips Tice Architecture. Adam Doll is Estimator/Project Manager and Alan Carlyle is Superintendent.



Dillon Credit Union: Hutchinson, KS

Only one Dillon Credit Union location has served the Hutchinson area since 1958. Demolition began mid November on a new 8,000 sq. ft. facility at 2704 N. Lorraine in Hutchinson, KS. Completion is expected in June. The building will be a traditional wood framed structure with a brick veneer. The interior offices and teller line will be showcased by a dark, oak trim. Dan Link of Landmark Architects, Hutchinson, KS designed the building. Adam Doll is the Estimator/ Project Manager. Marty Kerr is the Job Superintendent.

